



Riviera Playhouse

Model: 1536

(BOXES: 1518, 1528, 1529, 1536 & Accessory Box)

Copyright © 2016 PlayNation Play Systems, Inc. All Rights Reserved



190 Etowah Industrial Court Canton, GA 30114 www.playnation.com

52-3036-W



Please inspect and inventory all parts immediately upon accepting delivery. Use the inventory pages in the manual to make sure you have received all necessary parts. The quickest method to get any parts that are missing or damaged is use our "Quick Response Center" located at:

www.playnation.com/support

DO NOT RETURN THIS PRODUCT TO THE RETAILER OR CONTACT THE RETAILER DIRECTLY. THE RETAILER DOES NOT STOCK COMPONENTS.

PLEASE RETAIN ALL INSTRUCTIONS FOR FUTURE REFERENCE. KEEP THEM IN A SAFE PLACE WHERE YOU CAN REFER TO THEM AS NEEDED. CHECK FOR REVISED INSTRUCTIONS AT:

http://www.playnation.com/manuals.html

MANUFACTURER'S LIMITED LIFETIME WARRANTY

PlayNation Play Systems, Inc. warrants its Lifetime[™] series of swing sets to be free from defects in workmanship and materials, under normal use and conditions, for the lifetime of the product for above ground structural wood components and for two years for all other components (e.g., swings, hardware, plastics, tarps, rope ladder, etc.) except PlayNation's Super Scoop Slides[™] and Super Tube Spiral Slides[™].

PlayNation warrants its Super Scoop Slides[™] and Super Tube Spiral Slides[™] to be free from defects in workmanship and materials, under normal use and conditions, for the lifetime of the product.

PlayNation warrants its Regal[™], Imperial[™], and Empire[™] series swing sets to be free from defects in workmanship and materials, under normal use and conditions, for a period of 15 years for above ground structural wood components and for two years for all other components (e.g., swings, hardware, plastics, tarps, rope ladder, etc.).

PlayNation warrants all remaining products, including but not limited to its Free Standing Swing Set, Free Standing Tire Swing, See-Saw, Children's Picnic Table with Umbrella, Play-Zee-Bo[™], Riviera Playhouse and spring riders to be free from defects in workmanship and materials, under normal use and conditions, for a period of 1 year. All accessories purchased separate from those included with one of our swing set packages have a one year limited warranty.

<u>Cosmetic imperfections and natural tendencies of wood such as peeling, splintering, warping,</u> <u>seasonal checking or cracking, knots or knot holes, etc. are normal characteristics of all outdoor</u> <u>wooden play equipment and are not covered by this warranty. Checks or cracks in wood components</u> <u>that do not affect the intended function of the part, piece or overall swing set are not covered under</u> <u>this warranty.</u>

Wood rot or decay that develops because the product was installed in an area with poor drainage is not covered under this warranty. Lumber that has been damaged by wood boring bees, or conditions that develop as a result of faulty or improper installation of the product, are not covered by this warranty. Fading of stain, discoloration or mold on any wood part or accessory is not covered by this warranty. Cracks in plastic components, surface rust on hardware and chips on powder coated materials are not considered defects in material as long as they do not affect the functionality or structural integrity of the part or component.

It is the owner's responsibility to maintain the swing set. <u>This includes but is not limited to staining and</u> <u>sealing the lumber as needed and regular inspection to be sure all hardware is tight.</u> Instructions for proper maintenance can be found on PlayNation's website. Imperfections or conditions that develop because of a failure to properly maintain the swing set are not covered by this warranty.

PlayNation will, at its discretion, replace any above ground part within the stated warranty period that is defective in workmanship or materials. This decision is subject to verification of the defect, which, at PlayNation's discretion, may be accomplished by submitting photographs or by delivery of the defective part to PlayNation. PlayNation Play Systems, Inc. • 190 Etowah Industrial Ct. • Canton, GA 30114 • 770-704-9300 Monday to Friday 9AM-5PM EST. Any warranty claim must include proof of purchase, including the date of purchase. In addition, within the first 30 days from the date of purchase, PlayNation will replace any parts discovered to be missing from or damaged in the original packaging.

This warranty is valid only if the product is used for the purpose for which it was designed and installed at a residential, single-family dwelling. This warranty is void if the product is used in a commercial, institutional or multi-family setting. This warranty does not cover normal wear and tear or (a) products that have been damaged by acts of God and/or nature, negligence, misuse or accident; (b) products that have been modified or repaired by unauthorized persons; (c) the cost of labor; or (d) the cost of shipping any replacement product or part.

PLAYNATION DISCLAIMS ALL OTHER REPRESENTATIONS AND WARRANTIES OF ANY KIND, EXPRESSED, IMPLIED, STATUTORY OR OTHERWISE, INCLUDING THE IMPLIED WARRANTIES OF MERCHANTABILITY AND FITNESS FOR A PARTICULAR PURPOSE. PLAYNATION WILL NOT BE LIABLE FOR ANY INCIDENTAL OR CONSEQUENTIAL DAMAGES. This warranty is non-transferable and does not extend to the owners of the product subsequent to the original purchaser. Some states do not allow limitations on implied warranties or exclusion of incidental or consequential damages, so these restrictions may not be applicable to you. This warranty gives you specific legal rights. You may also have other rights which vary from state to state.

IMPORTANT SAFETY GUIDELINES

This product is recommended for use by children ages 3-11. This product is intended for residential use only and not intended for use in any public setting. A safety surface such as mulch or recycled tire should be used under the play set to prevent injury from falls. Also a 6 foot safety zone should be used around the entire play set.

As with any home project, good judgment and respect for power tools will greatly reduce the risk of injury. PlayNation recommends you follow all tool manufacturers' safety guidelines. Always wear eye protection and safety gloves to prevent injury. In several phases of construction two people may be required for lifting and securing of lumber. While the play set is being constructed, please keep children off the equipment until the project is complete. Bolts and screw heads should be checked regularly for tightness. The ground ladder, rope ladder, slide, swings and other areas where children spend a majority of their playtime should be checked more frequently.

PlayNation shall not be liable for incidental, indirect or consequential damages or injuries that result from the building and/or playing on our play sets. Adult supervision is recommended anytime a play set is being used.

WEIGHT LIMITS FOR PLAYNATION PLAYSETS

- FORT PLATFORMS: 800 LBS. TOTAL WEIGHT
- SWING BELT: 225 LBS.
- TANDEM SWINGS: 70 LBS. PER CHILD. UP TO 140 LBS TOTAL WEIGHT.
- TRAPEZE: 125 LBS.
- FULL BUCKET SWING/ HALF BUCKET SWING: 50 LBS.
- HEAVY DUTY TODDLER BUCKET SWING: 85 LBS.
- INFANT SWING: 35 LBS.
- TIRE SWING: 125 LBS. TOTAL WEIGHT
- ROPE LADDER: 75 LBS.
- ROCK WALL: 150 LBS.
- CLIMBING RAMP: 150 LBS.
- MONKEY BARS: 175 LBS.
- ALL SLIDES: 150 LBS.

PlayNation recommends that the weight limits for all components must not be exceeded. Failure to adhere to these and other safety guidelines could result in damage to the play set and injury to the users.

THIS PAGE INTENTIONALLY LEFT BLANK

WARRANTY REGISTRATION

- RIVIERA PLAYHOUSE -

PlayNation[™] manufactures the finest quality products that are designed for outstanding strength and durability. We back our products with an unparalleled warranty. In the unlikely event that you will need to contact us about covered repairs, we must have a valid Warranty Registration on file.

| 3 EASY WAYS TO REGISTER | | |
|-------------------------|--------------------------------------------------------------------------------------------------------|--|
| OPTION 1 | Complete the online registration form at: http://www.playnation.com/register | |
| OPTION 2 | Fax this completed form to: (678) 880-3300 | |
| OPTION 3 | Mail this completed form to: PlayNation Playsets 190 Etowah Industrial Court Canton, GA 30114 | |

Where did you buy this product?

| Date of Purchase | Sto | pre | | (| Store City | Store State |
|------------------|-------------|---------------------|----------------------|--------------|---------------------|---------------|
| Your registra | tion inforr | nation: | | | | |
| Name: | | | Email: | | | |
| Address: | | | | | | |
| Street | | | City | | State | Zip |
| Please select | 18-30 | 41-50 | How would | | *** | ★ Excellent |
| your age | 31-40 | 51+ | you rate the | $\Box \star$ | $\star \star \star$ | Above Average |
| | | | quality of this | $\Box \star$ | ★ ★ Avera | age |
| How old are | 2-3 | 6-7 | product? | | Helow Aver | rage |
| your children? | 4-5 | 8+ | | $\Box \star$ | Poor | |
| Would you reco | ommend this | s product to frienc | ls & family? 🗌 Yes 🗌 |] No | | |
| Comments: | | | | | | |
| | | | | | | |
| | | | | | | |

THIS PAGE INTENTIONALLY LEFT BLANK

IMPORTANT – PLEASE READ

Congratulations! You have just purchase one of the finest residential wooden swing sets available today. As with any wooden product that spends its entire life outside, in varying elements, it is important to know what to expect with your new swing set so that your family can enjoy it for many years.

As your swing set acclimates to its new environment, natural characteristics of the wood can show in the form of checks, or "cracks" in the lumber. In almost all cases this is normal and it will not affect the structural integrity of your play set and is not covered under warranty.

KEEPING YOUR PLAYSET LIKE NEW

MUST DO's

The following owner responsibilities are crucial to the safety, integrity and aesthetic appeal of your swing set and may affect the warranty if not adhered to.

WITHIN 60 DAYS

• Check and tighten Hex Bolts/T-nuts, Carriage Bolts/Lock-nuts, and Lag Screws within the first 60 days and then twice annually – once before each season and then once during the season.

WITHIN 90 DAYS

• Apply a **sealant** or **semi-transparent stain with sealant** within the first 90 days of owning the swing set. If applicable state laws allow, an oil based product will penetrate and protect the lumber better than a water based product. Because climate conditions can vary drastically from region to region, we suggest asking the product covering specialists at any number of specialty paint stores or home improvement centers for a product that would work best for your local environment. ** TIP – while the set is new, take a small board from your swing set to the store with you so they can color match the tint of the stain or sealant. Be sure to replace the board when you get home.

SEASONAL REMINDERS

If your area experiences regular snowfall, remove your fabric tarp/canopy to avoid stretching, sagging or tearing of the material. Store it inside, folded up, and it will be as good as new when winter is over.
If your area experiences extremely cold temperatures, remove swing belts and other pliable features to

• If your area experiences extremely cold temperatures, remove swing belts and other pliable features to prolong the lifespan of these play activities.

OTHER TIPS

• Spray swing hangers with Pam, Mazola or olive oil to stop squeaking; do not use petroleum based products such as WD-40 or motor oil.

• To repel yellow jackets and wasps, use a cotton ball and dab interior wooden corners underneath the play set deck with a liquid dish soap. Avoid using insecticides.

• To speed up the slide wipe the <u>center</u> of slide with wax paper every 2 - 3 weeks.

For additional safety and maintenance guidelines, please visit our website.



IMPORTANT DOCUMENTS CUSTOMER MUST READ AND RETAIN

Please go to the following links and read important SAFETY information prior to using your new play structure.

http://www.playnation.com/safety-and-maintenance.html

http://www.playnation.com/manuals.html (Click on your specific model)

http://www.playnation.com/warranty.html

NOTE: Your children's safety is our #1 concern. Observing the following statements and warnings reduces the likelihood of serious injury. Please review these safety rules regularly with your children.

WARNING:

Children must NOT use this play set until it has been completely assembled and inspected by an adult to ensure it has been properly installed.

> PlayNation Play Systems, Inc. 190 Etowah Industrial Court Canton, GA. 30114



Model: 1536

(BOXES: 1518, 1528, 1529, 1536 & ACCESSORY BOX)

REV: 11.17.2016

TABLE OF CONTENTS

| Safety Guidelines | Pages 3-6 |
|------------------------------------------------------------------------------|-------------|
| Leveling Fort, General Information and Definitions | Pages 6-8 |
| How to Install T-Nuts, Board Identification, Predrill Lag Screw Directions . | Pages 9-12 |
| Site Plan, Required Tool List and Kit Contents | Pages 13-14 |
| Hardware, Lumber and Accessory Checklists | Pages 15-28 |
| Framing the Playhouse | Steps 1-9 |
| Wood Roof Assembly | Steps10-15 |
| Front Gable Assembly | Step 16 |
| Bottom Wall Board | Step 17 |
| Attaching Front Gable | Step 18 |
| Wall Panel Supports and Roof Finishers | Steps 19-20 |
| Roof Battens | Step 21 |
| Wall Panel Boards and Roof Gable Boards | Steps 22-23 |
| Dormer Assembly and Installation | Step 24 |
| Wall Boards-Left, Rear and Right Sides | Steps 25-33 |
| Panel Slats | Steps 34-35 |
| Drilling for Front Accent pieces and Installating them | Step 36-37 |
| Solar Wall Lights | Step 38 |
| Lemonade Stand sign | Steps 39-40 |
| Logo Plate | Step 41 |
| Appendix | Page 70 |

PLEASE READ OWNER'S MANUAL CAREFULLY BEFORE STARTING ASSEMBLY!

Safety and Maintenance Tips for Your New Play Set:

NOTE: Your children's safety is our #1 concern. Observing the following statements and warnings reduces the likelihood of serious or fatal injury. Please review these safety rules regularly with your children.

- This play set is designed for the use of 4-6 occupants.
- On-site adult supervision is required.
- Teach children not to use the equipment in a manner other than intended.

• The parents should have the children dress appropriately with well-fitting shoes. Loose clothing such as scarves and ponchos should not be worn. Always take off, tie up or tuck in cords and drawstrings on children's clothing. These things can get caught on playground equipment and strangle a child.

• Teach children not to climb on the playhouse railings, serving window, window or roof.

• Teach children not to attach items to the playground equipment that are not specifically designed for use with the equipment, such as, but not limited to, jump ropes, clothesline, pet leashes, cables and chain as they may cause a strangulation hazard.

• Teach children to remove their bike or other sports helmet before playing on the playgound equipment.

• Teach children to NEVER look at the sun or other bright light through any accessory such as but not limited to a telescope, periscope or binoculars.

WARNING: Children must NOT use this play set until it has been completely assembled and inspected by an adult to insure it has been properly installed.

Safety and Maintenance Tips for Your New Play Set: (continued)

Playgrounds should be inspected on a regular basis. If any of the following conditions are noted, they should be removed, corrected, or repaired immediately to prevent injuries.

• Hardware that is loose, worn or that has protrusions or projections.

• Exposed equipment footings.

• Scattered debris, litter, rocks, or tree roots.

- Splinters, large cracks, and decayed wood components.
- Deterioration and corrosion on structural components, which connect to the ground.

• Missing or damaged equipment components, such as handholds, guardrails, swing seats.

• Check all nuts and bolts twice monthly during the usage season and tighten as required.

(But not so tight that you crack the wood) We recommend you check the hardware often due to wood expansion and contraction. It is particularly important that this procedure be followed at the beginning of each season.

• Check all coverings for bolts and sharp edges twice monthly during usage season to be certain they are in place. Replace when necessary. It is especially important to do this at the beginning of each new season.

• For rusted areas on metallic members such as monkey bars, hand supports brackets, etc.; sand and repaint, using a non lead-based paint meeting the requirements of Title 16 C.F.R. Part 1303. These requirements are available at: http://www.cpsc.gov/

• Inspect wood parts monthly. The grain of the wood sometimes will lift in the dry season causing splinters to appear. Light sanding may be necessary to maintain a safe playing environment. If you are treating your play set with stain regularly, it will help prevent severe checking/splitting and other weather damage.

• Once or twice a year, depending on your climate conditions, you must apply some type of protection (sealant) to the wood of your unit. Prior to the application of sealant, lightly sand any "rough" spots on your set. Please note this is a requirement of your warranty.

• Creating and maintaining the play set on a level location is very important. As your children play, your play set will slowly dig its way into the soil, and it is very important that it settles evenly. Make sure the play set is level and true once each year or at the beginning of each play season.

• Twice a month during the usage season rake the playground protective surfacing materials to prevent compaction and maintain appropriate depths. Replace the protective surfacing materials as required.

• Disposal Instructions: When the play set is no longer desired, it should be disassembled and disposed of in such away that no unreasonable hazards will exist at the time the play set is discarded.

Play Set Surfacing Recommendations:

Below are some of the recommendations that the U.S. Consumer Product Safety Commission (CPSC) offers from its Handbook for Public Playground Safety. The guide can be downloaded in full at www.cpsc.gov/cpscpub/pubs/325.pdf

1. Protective Surfacing - Since almost 60% of all injuries are caused by falls to the ground, protective surfacing under and around all playground equipment is the most critical safety factor on playgrounds.

Certain manufactured synthetic surfaces also are acceptable; however, test data on shock absorbing performance should be requested from the manufacturer.

Asphalt and concrete are unacceptable. They do not have any shock absorbing properties. Similarly, grass and turf should not be used. Their ability to absorb shock during a fall can be reduced considerably through wear and environmental conditions.

Certain loose-fill surfacing materials are acceptable. Surfacing materials are acceptable, such as the types and depths shown in the table.

| Type Of Material | 6 in. depth | 9 in. depth | 12 in. depth |
|----------------------------|--------------------|-----------------|-----------------|
| Double-Shredded bark mulch | 6' Fall Height | 10' Fall Height | 11' Fall Height |
| Wood Chips | 6' Fall Height | 7' Fall Height | 12' Fall Height |
| Fine Sand | 5' Fall Height | 5' Fall Height | 9' Fall Height |
| Shredded Tires* | 10-12' Fall Height | N/A | N/A |
| Fine Gravel | 6' Fall Height | 7' Fall Height | 10' Fall Height |

Fall Heights and Materials

*This data is from tests conducted by independent testing laboratories on a 6-inch depth of uncompressed shredded tire samples produced by four manufacturers. The tests reported critical heights, which varied from 10 feet to greater than 12 feet. It is recommended that persons seeking to install shredded tires as a protective surface request test data from the supplier showing the critical height of the material when it was tested in accordance with ASTM F1292.

It should be recognized that all injuries due to falls cannot be prevented no matter what surfacing material is used.

2. Fall Zones - A fall zone, covered with a protective surfacing material, is essential under and around equipment where a child might fall. This area should be free of other equipment and obstacles onto which a child might fall. Stationary climbing equipment and slides should have a fall zone extending a Minimum of 6' in all directions from the perimeter of the equipment.

Swings should have a fall zone extending a minimum of 6' from the outer edge of the support structure on each side. The fall zone in front and back of the swing should extend out a minimum distance of twice the height of the swing as measured from the ground to the top of the swing support structure.

LEVELING YOUR FORT DURING ASSEMBLY

• Complete the steps which will be the basic frame of the fort. {i.e. four corner posts with base (sand box boards) and deck supports}

• Position in the most level area chosen for the play set, keeping in mind the location and size of the swing beam, ladder, slides, etc. that extend off the fort.

• Once the frame is in the final position, check for vertical and horizontal levelness to determine which side(s) will need to be dug into the ground to level the play set.

• With a shovel, score the ground around the outside edges of the sandbox boards on the 'high' side of the fort. This is the area that will be dug in. Make sure to score deep enough; the scored lines will be your digging template.

• Push the frame off and away from the scored area, far enough to dig and remove dirt to reach the appropriate depth.

• Dig a channel along the scored line(s) for the base of the fort (corner post and sandbox boards) to rest into. Dig the channel(s) to the same level depth. The bottom of the channel(s) should be level to each other so your frame doesn't teeter or rock because the channel(s) are uneven.


• Once you have removed enough grass and dirt, slide/push the frame into the channel(s). Place a level on the vertical and horizontal boards of the frame to determine if enough soil, or too much, was removed.

• Repeat this process until the basic frame is plumb and level and in its final position before completing the rest of the assembly.

• Measure to make sure fort is square.

Important: if you require a channel depth of more than 6", then we recommend you have your play set area professionally graded before completing assembly.

Example Play area:





The diagonal measurements should be the same from corner post to corner post. If not, adjust corner posts so that the distance is equal.

Area to be scored and channeled for levelness

General Info to Review Before Installation

• Depending on your experience, assembly of the playset can take as little as 6 hours up to 24 hours, depending on size, after inventory of parts; therefore, we recommend you set aside a full two days for assembly.

• Identify all of the parts for your play set. Empty each box and lay out boards so you can see each part. Your instruction book will have detailed drawings that will make it easy for you to recognize individual parts. Keep all hardware and metal parts separate from wooden pieces.

• After everything is laid out, check carefully to ensure all parts are present. Make sure there are no broken boards.

• Find an area to sort your hardware. It is best to open the hardware on a solid surface so that you do not lose any pieces in the grass. This will save time and familiarize you with all the different pieces in the hardware bag.

• Important note: Wood has some natural defects such as knots, surface cracks, etc... We reject parts that are structurally defective. We use a high quality lumber in our structures; however, you should inspect each part for splinters or rough spots and sand them smooth to prevent injury.

• After familiarizing yourself with all of the components, read all instructions thoroughly. Reading instructions after you have studied the parts will help you understand the installation process, and help to eliminate unnecessary mistakes.

• Pay close attention to the diameter and length of each bolt and screw.

• Never tighten hardware completely at first. It helps to have some adjustment for bolt alignment while you are attaching parts together. After everything is square, tighten each joint.

• After the main unit is assembled it is critical that the floor is level and square. If the main frame is not level, the walls and floor will be out of square.

• After you complete installation, make sure every bolt, screw, and nut is tight, and every board is secure. Wood will expand and contract with the seasons.

• Place the set on level ground, not less than 6 feet from any structure or obstruction such as a fence, garage, house, overhanging branches, laundry lines, or electrical wires.


This page is a list of definitions and explanations used throughout our instructions to aid you in the assembly of your play set.

Offset Holes- Throughout the installation procedures we will refer to parts with offset holes. This refers to the orientation of the holes on the board. An offset hole is one that is closer to one side than it is the other or in other words, it is not centered on the board. In the procedures you will be instructed to attach the boards with the holes offset up or with the holes offset down. This refers to which side of the board the hole/holes should be closer to. Offset holes up= hole/holes will be closer to the top of the board. Offset holes down= hole/holes will be closer to the bottom of the board. Note: some parts do not have offset holes, but instead the holes are on center. Therefore there will not be any reference on how to offset these parts.

EXAMPLE OF OFFSET HOLES UP




Counter-sunk holes - Many of the parts that will be used have counter-sunk holes. A counter-sunk hole is one that surrounds one side of a through hole, but does not extend through the wood it's self. When using a counter-sunk hole the bolt will be inserted through the through hole and either the head of the bolt and washer or nut and washer will occupy the counter sunk hole.




Lag Screws- Lag screws are used in the construction of our play sets to enhance the structural integrity of the unit. There will not be predrilled holes in the post for lag screw installation. Lag screws are self-tapping, though if you are using a manual socket wrench it may be advantageous to pre-drill a hole first. Instructions for this are provided on a separate page in the front of the manual. Be sure to tighten the lags completely when driving them in by hand. Power tools such as a heavy duty impact driver or large power drill should have enough torque to drive in the lag screws, but make sure not to over tighten as this can cause the threads to "strip out" in the post.

Common Installation Practice Installing T-nuts

When installing T-nuts into the wood, use a smooth faced hammer to set the face of the T-nut flush into the wood.








Insert the barrel of the T-nut into the predrilled hole. Using a smooth faced hammer, drive the T-nut until the face of the T-nut is flush to the wood.



This picture shows an end view of the T-nut installed flush to the wood.

WARNING: DO NOT EMBED THE TOP OF THE T-NUT INTO THE FACE OF THE WOOD




Cross Section end view, you are looking at an X-ray view of the post and T-nut. The barrel of the T-nut is in the corner post the line is the face of the wood.

HOW A T-NUT WORKS

THE FIRST STEP IN OUR ASSEMBLY INSTRUCTIONS IS TO INSERT T-NUTS INTO THE CORNER POSTS. A T-NUT IS A FASTENER WHICH IS THREADED ON THE INSIDE AND IT FUNCTIONS JUST LIKE A STANDARD HEX NUT. YOU INSERT THE T-NUTS INTO THE PREDRILLED HOLES IN THE CORNER POSTS.

THE T-NUT HAS A BARREL SHAPED END WHICH GOES INTO THE HOLE IN THE CORNER POST. THE T-NUT ALSO HAS AN FLANGE SHAPED END WITH TEETH. THE TEETH PENETRATE INTO THE CORNER POST WOOD TO PREVENT THE T-NUT FROM SPINNING WHEN YOU TIGHTEN THE HEX HEAD BOLT.

SHOWN BELOW YOU WILL SEE THE T-NUT IS HAMMERED INTO THE CORNER POST ON THE BACK SIDE. THE BOARD IS BEING ATTACHED ON THE FRONT SIDE OF THE CORNER POST.



BOARD IDENTIFICATION


1. On the end of each board there should be a small white tag that is stapled or stuck into place. Remove the staples and/or tag after the board is installed.

2. This white identification tag displays the thickness, width, length and an abbreviated description of the part.

Example: a tag reads "2-4-3600-BPB"

- The 2 is the thickness of the board. "Nominal Lumber" at a home center will measure 1-1/2" for the thickness. We "remill" that lumber to 1-3/8" thick.
- The 4 is the width of the board. "Nominal Lumber" at a home center will measure 3-1/2" for the width. We "remill" that lumber to 3-3/8" wide. Note: sometimes the width will be smaller than 3-3/8" because:
 A) We need the width of the part to fit into a certain area of the play set.
 B) We need the designation to be simple.
- The 3600 is the length of the board. It means the board is 36 inches long. If the code were 3625 then the board is 36-1/4" in length.
- The "BPB" abbreviation stands for "Bottom Panel Board". The wood part bill of materials in the instructions has a description which will match the abbreviation closely.
- In the event that there is no tag on a wood part measure the part then:

 A)Use the measurements and compare them to the wood list at the front of the instructions to identify it.
 B)Look at the holes on the wood part and compare them to the pictures in the wood list.
 C)Look to see if the holes are centered or if they are offset up or offset down.
 This should help you identify any parts that have missing tags. In the event that you cannot identify a board please email us for assistance.



PRE-DRILL LAG SCREW DIRECTIONS

Pre-drilling holes for lag screws will make it easier to drive the screws in by hand. "Jobber" length drill bits are available in sizes that are longer than standard drill bits and those are ideal for the job. When using the drill bit you will have to "spot" drill the post and then remove the board you are attaching to finish drilling the hole.

Pay attention to the DIAMETER of the lag screw you are installing. Your playset may come with two different diameter lag screws. Each diameter will require a different size drill bit. When installing lag screws **DO NOT OVERTIGHTEN**.

| LAG SCREW DIAMETER | DRILL BIT SIZE |
|--------------------|----------------|
| 5/16" DIAMETER | 9/64'' |
| 3/8" DIAMETER | 11/64" |

Example: 3/8" diameter x 3-1/2" lag screw

This would be like the 2×4 board installation shown below. Place the board into position. Spot Drill through the holes in the 2×4 board into the corner posts with an 11/64" drill bit. Remove the 2×4 board. Continue to drill the holes to a total depth of 2-5/16" as shown at the right. Install the 2×4 board.

Example 5/16" diameter x 3-1/2" lag screw

This would be like the 2×4 board installation shown below. Place the board into position. Spot Drill through the holes in the 2×4 board into the corner posts with an 9/64" drill bit. Remove the 2×4 board. Continue to drill the holes to a total depth of 2-5/16" as shown at the right. Install the 2×4 board.



Example 3/8" diameter x 5" lag screw


This would be like the 4 x 4 board installation shown below. Place the board into position. Spot drill through the holes in the 4 x 4 board into the corner posts with an 11/64" drill bit. Remove the 4 x 4 board. Continue to drill the holes to a total depth of 2-13/16" as shown at the right. Install the 4 x 4 board.







Please familiarize yourself with the manual, parts/components and general construction process of your new playset before getting started.

SITE PLAN:







Playset height:83"

Interior Dimensions:

Width-68-1/2" Depth-45-3/4" Height at front/rear-55-1/2" Height at center (roof peak) 75-1/2"

Other dimensions (rounded off): Door Opening-21-1/2"W x 39-3/4" H Serving Window Opening-29-3/4"W x 12-3/4"H(at center) Serving Window Top Height- 29-3/4" Front Wall Height to top of railing-29"

Approximate assembly time: 12 to 16 hours

(6) foot unobstructed safety perimeter around playset recommended

REQUIRED TOOL LIST:

- ____ Standard or Cordless Drill w/ Phillips Bit (#2 square bit provided)
- ____ Drill Bits 1/16", 1/8", 3/8", 9/64"
- ____1⁄2" Wrench and Socket
- ____12" Deep Well Socket
- ____ Level
- ____ Tape Measure
- ____ Extension Cord (if using standard drill or jigsaw)
- ____ Hammer
- ____ Pencil
- You may need a Saw (handsaw or jigsaw) See Step 20
- ____ Pliers and/or Locking Pliers (Vise Grips)
- ____ Carpenter's Square
- ____ Shovel (if installing outdoors)

KIT CONTENTS

Swings, Slides, Accessories:


- (Qty) Description
- (2) Plastic Sunburst
- (1) Plastic Front Arch
- (2) Plastic Dormer Window
- (2) Solar Wall Light
- ____(1) Logo Plate
- ____(1) Plastic Window with shutters
- ____ (1) Lemonade Stand Sign


Hardware:


see following pages


Wood Components:

see following pages









| PICTURE | DESCRIPTION | QTY. |
|---------|------------------------------------------------------------------|----------------|
| | 1 X 2 X 32" ROOF BATTEN 1-2-3200-RB | 2 |
| | 1 X 4 X 8-3/4" WALL PANEL BOARD 1-4-0875-WPB | 2 |
| | 1 X 4 X 12-1/4" Wall Panel Board 1-4-1225-WPB | 2 |
| | 1 X 4 X 15-3/4" WALL PANEL BOARD 1-4-1575-WPB | 2 |
| | 1 X 4 X 19-5/16" WALL PANEL BOARD 1-4-1931-WPB | 2 |
| | 1 X 4 X 29-1/4" Roof finisher Front left 1-4-2929-RFFL | 1 |
| | 1 X 4 X 29-1/4" Roof finisher Front right 1-4-2929-RFFR | 1 19 |

| | PICTURE | DESCRIPTION | QTY. |
|------|---------------------------------------|-----------------------------------------------------------------|----------------|
| | | 1 X 4 X 76-7/8" ROOF FINISHER REAR 1-4-7688-RFR | 1 |
| 4.00 | · · · · · · · · · · · · · · · · · · · | 1 X 4 X 76-7/8" Roof starter Front 1-4-7688-RSF | 1 |
| 3.25 | | 1 X 4 X 76-7/8" Roof starter Rear 1-4-7688-RSR | 1 |
| | | 1 X 5 X 76-7/8" ROOF BOARD 1-5-7688-RB | 14 |
| | | 2 X 4 X 22-3/4" WALL PANEL SUPPORT LEFT 2-4-2275-WPSL | 1 |
| | | 2 X 4 X 22-3/4" WALL PANEL SUPPORT RIGHT 2-4-2275-WPSR | 1 |
| | NOT USED | 2 X 4 X 28-9/16" CENTER POST 2-4-2856-CPFR | 2 20 |

| PICTURE | DESCRIPTION | QTY. |
|---------|----------------------------------------------------------------------|----------------|
| | 2 X 4 X 35-3/16" ROOF SUPPORT LEFT 2-4-3515-RSL | 2 |
| | 2 X 4 X 35-3/16" ROOF SUPPORT RIGHT 2-4-3515-RSR | 2 |
| 0 | 2 X 4 X 69-3/4" ROOF FINISHER SUPPORT 2-4-6975-RFS | 1 |
| | 5/4 X 6 X 10" ROOF PEAK SUPPORT 125-6-1000-RPS | 2 |
| | 5/4 X 5 X 10-7/8" ROOF PANEL PEAK SUPPORT 125-5-1081-RPPS | 1 |
| | 5 X 11 X 46-15/16" ROOF PANEL LEFT ASSEMBLY 5-11-4697-RPLA | 1 |
| | 5 X 11 X 46-15/16" ROOF PANEL RIGHT ASSEMBLY 5-11-4697-RPRA | 1 21 |

| PICTURE | DESCRIPTION | QTY. |
|---------|-----------------------------------------------------------------------|---------|
| 1518 | 1 X 3 X 18" WINDOW TOP BOARD 1-3-1800-WTB | 1 |
| | 1 X 3 X 29-7/8" Open Window Outside Support 1-3-2988-OWOS | 1 |
| | 1 X 3 X 34-3/4" WINDOW BOTTOM BOARD 1-3-3475-WBB | 1 |
| | 1 X 3 X 40-1/2" PANEL BOARD BRACE 1-3-4050-PBB | 2 |
| • | 1 X 4 X 9" TOP BOARD WINDOW 1-4-0900-TBW | 3 |
| + | 1 X 4 X 10" OPEN WINDOW TOP BOARD 3 1-4-0998-OWTB3 | 2 |
| • | 1 X 4 X 27-3/4" BOTTOM WINDOW BOARD 1-4-2775-BWB | 5 22 |

| PICTURE | DESCRIPTION | QTY. |
|---------|------------------------------------------------------------------|----------------|
| | 1 X 4 X 29-1/2" OPEN WINDOW BOARD 1-4-2950-OWB | 1 |
| · · | 1 X 4 X 51" WALL BOARD 1-4-5100-WB | 6 |
| * | 1 X 6 X 8-7/16" TOP BOARD DOOR 2 1-6-0843-TBD2 | 2 |
| * | 1 X 6 X 10-3/16" TOP BOARD DOOR 1 1-6-1020-TBD1 | 2 |
| + | 1 X 6 X 11-3/16" Open Window Top Board 2 1-6-1118-OwtB2 | 2 |
| + | 1 X 6 X 13-5/8" OPEN WINDOW TOP BOARD 1 1-6-1360-OWTB1 | 2 |
| | 1 X 6 X 27" ARCH TOP BOARD DOOR 1-6-2700-ATBD | 1 23 |

| PICTURE | DESCRIPTION | QTY. |
|---------------------------------------|--------------------------------------------------------------------|----------------|
| | 1 X 6 X 27-3/4" BOTTOM BOARD OPEN WINDOW 1-6-2775-BBOW | 4 |
| · · · · · · · · · · · · · · · · · · · | 1 X 6 X 34" TOP BOARD WINDOW 1-6-3400-TBW | 1 |
| | 1 X 6 X 51" WALL BOARD 1-6-5100-WB | 11 |
| NOT USED | 2 X 4 X 47-1/2" TOP PANEL BOARD 2-4-4750-TPB | 1 |
| 1 IS NOT USED | 2 X 4 X 70" BOTTOM WALL BOARD 2-4-7000-BWB | 2 |
| | 2 X 6 X 70" Bottom Panel Board Door 2-6-7000-BPBD | 1 |
| | 5/4 X 6 X 28-1/4" PANEL SLAT 125-6-2825-PS | 7 24 |

| PICTURE | DESCRIPTION | QTY. |
|---------|----------------------------------------------------------|----------------|
| 1536 | 5/4 X 4 X 20-3/4" VERTICAL ACCENT 125-4-2075-VA | 1 |
| | 5/4 X 4 X 28-3/8" DIAGONAL ACCENT 125-4-2838-DA | 2 |
| | 2 X 6 X 42" Roof Gable Board 2-6-4200-RGB | 2 |
| | 2 X 5 X 47-1/2" BOTTOM PANEL BOARD 2-5-4750-BPB | 2 |
| | 2 X 5 X 70" SANDBOX BOARD 2-5-7000-SB | 1 |
| | 4 X 4 X 51-1/4" Front corner Post 4-4-5125-FCP | 2 |
| | 4 X 4 X 51-1/4" REAR CORNER POST 4-4-5125-RCP | 2 25 |

| PICTURE | DESCRIPTION | QTY. |
|---------|--------------------------------------------------|------|
| | 5/4 X 3 X 28-1/4" PANEL SLAT 125-3-2825-PS | 8 |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | 26 |


| PICTURE | DESCRIPTION | QTY. |
|-------------|------------------------------------------|----------------|
| | PLASTIC SUNBURST 07-0028-G | 2 |
| | PLASTIC FRONT ARCH 07-0027-G | 1 |
| | PLASTIC DORMER WINDOW 07-0029-G | 2 |
| | SOLAR WALL LIGHT 09-2003 | 2 |
| (NOT SHOWN) | MANUFACTURER LOGO PLATE | 1 |
| | UNASSEMBLED DORMER (1529 BOX) | 2 |
| | UNASSEMBLED CHIMNEY (1529 BOX) | 1 27 |


| PICTURE | DESCRIPTION | QTY. |
|------------------|-----------------------------------------------------------|------|
| | PLASTIC WINDOW 07-0013 | 1 |
| | LEMONADE STAND SIGN 07-0024 | 1 |
| 1528, 1518, 1536 | HARDWARE KITS | 1EA |
| (NOT SHOWN) | TOUCH UP STAIN (LITTLE BOTTLE THAT IS BAGGED) | 1 |
| | | |
| | | |
| | | 28 |


STEP 1: RIGHT SIDE


1: HAMMER T-NUTS INTO THE CORNER POSTS HOLES THAT ARE 3" OFF THE BOTTOM. TIP: USE A SCREWDRIVER OR A 4-1/2" HEX BOLT TO CLEAN OUT THE HOLES IF SAWDUST IS PRESENT. IF THE HOLES ARE SLIGHTLY SMALL THEN REAM THEM OUT WITH A 3/8" DRILL BIT.

2: FASTEN THE 2 X 5 X 47-1/2" BOTTOM PANEL BOARD (OFFSET DOWN) TO THE CORNER POSTS WITH 5/16" X 4-1/2" HEX BOLTS AND 5/16" WASHERS.









STEP 5: ROOF SUPPORT


1: PLACE THE 2 X 4 X 35.15 ROOF SUPPORTS ON A FLAT SURFACE AS SHOWN. THE COUNTERBORES SHOULD BE FACING THE GROUND (FLAT SURFACE).

2: USE A CARPENTER'S SQUARE TO ENSURE THE PARTS ARE SQUARE TO ONE ANOTHER.

3: PLACE THE 5/4 X 6 X 10" ROOF PEAK SUPPORT ON TOP OF THE ROOF SUPPORTS. THE EDGES OF THE ROOF PEAK SUPPORT SHOULD BE EVEN OR SLIGHTLY BELOW THE EDGES OF THE ROOF SUPPORTS.

4: ATTACH THE ROOF PEAK SUPPORT TO THE ROOF SUPPORTS WITH #8 X 2" WOOD SCREWS.

5: REPEAT SUBSTEPS 1THROUGH 4 TO MAKE ANOTHER ROOF SUPPORT ASSEMBLY.



STEP 6: PLASTIC SUNBURSTS


1: PLACE THE PLASTIC SUNBURST OVER THE ROOF SUPPORTS.

2: MAKE SURE THE ROOF SUPPORTS ARE STILL SQUARE TO ONE ANOTHER WITH THE CARPENTER'S SQUARE.

3: THE TOP SURFACES OF THE SUNBURST SHOULD BE FLUSH OR SLIGHTLY BELOW THE TOP SURFACES OF THE ROOF SUPPORTS.

4: FASTEN THE SUNBURST TO THE ROOF SUPPORTS WITH TWO #8 X 2-1/2" WOOD SCREWS AT THE TOP TRIANGLE SECTION AND SIX #8 X 2" WOOD SCREWS ON THE SIDES.

5: REPEAT SUBSTEPS 1 THROUGH 4 FOR THE OTHER ROOF SUPPORT ASSEMBLY.




STEP 7: ROOF SUPPORT ASSEMBLIES

1: HAMMER A T-NUT INTO THE TOP HOLE ON THE INSIDE OF EACH CORNER POSTS.

2: FASTEN THE ROOF SUPPORT ASSEMBLY TO THE LEFT SIDE WITH 5/16" X 4-1/2" HEX BOLTS AND 5/16" WASHERS.

3: REPEAT SUBSTEPS 1 THROUGH 2 FOR THE OTHER ROOF SUPPORT ASSEMBLY.




STEP 8: LEVEL AND SQUARE

1: NOW IS THE TIME TO LEVEL AND SQUARE UP THE FRAME.

2: MAKE SURE THE BOARDS AT THE BOTTOM ARE ALL LEVEL. MAKE SURE ALL THE POSTS ARE SQUARE TO THE BOARDS AT THE BOTTOM.

3: COMPARE MEASUREMENTS AT THE BOTTOM AND AT THE TOP OF THE POSTS. THE POSTS NEED TO BE PARALLEL TO ONE ANOTHER. IF THEY ARE NOT PARALLEL THEN LOOSEN THE HEX BOLTS AND MAKE THEM PARALLEL.




STEP 9: LAG SCREWS

1: THE FRAME SHOULD BE LEVEL AND SQUARE AT THIS POINT. THE POSTS SHOULD BE PARALLEL TO ONE ANOTHER ALSO.

2: USE A 9/64" DRILL BIT TO DRILL A PILOT HOLE AT EACH LOCATION SHOWN. (SEE PRE-DRILL LAG SCREW DIRECTIONS AT FRONT OF THE MANUAL FOR 5/16" X 3-1/2" LAG SCREWS.)

3: INSTALL A 5/16" X 3-1/2" LAG SCREW WITH 5/16" WASHER AT EACH LOCATION.

4: VERIFY THE POSTS ARE STILL PARALLEL TO ONE ANOTHER.




STEP 10: ROOF STARTER REAR

IT MAY BE HELPFUL TO TEMPORARILY INSTALL A ROOF BOARD AT THE BOTTOM OF THE ROOF SUPPORTS. THAT WAY YOU CAN POSITION THE PEAP POOF STARTER AND MAKE ADJUSTMENTS EASILY IN STEP 11.

1: FASTEN THE ROOF BOARD AT THE END OF THE ROOF SUPPORTS WITH #8 X 1-1/2" WOOD SCREWS.

2: MEASURE THE DISTANCE ACROSS THE SET AT THE TOP OF THE POSTS. THAT DISTANCE SHOULD MATCH THE BOTTOM OF THE POSTS. IF THAT DISTANCE IS NOT THE SAME THEN LOOSEN THE WOOD SCREWS IN THE ROOF BOARD AND REPOSITION ON ONE SIDE UNTIL THE DISTANCES MATCH.

THE ROOF SUPPORT ASSEMBLIES SHOULD BE VERTICAL. IF THEY ARE NOT THEN YOU WILL BE ABLE TO ADJUST THEM SOME IN THE NEXT STEP.




STEP 11: ROOF STARTER REAR

1: PLACE THE 1 X 4 X 76-7/8" ROOF STARTER REAR BOARD AT THE PEAK OF THE ROOF. THE HOLES IN THE ROOF STARTER SHOULD BE CENTERED ON THE ROOF SUPPORTS, AND THE FLAT TOP END OF THE ROOF STARTER SHOULD BE PLACED FLUSH TO THE PEAK OF THE ROOF SUPPORTS.

2: FASTEN THE ROOF STARTER REAR TO THE ROOF SUPPORTS WITH 1-1/2" WOOD SCREWS.

MEASURE DIM A ACROSS THE BOTTOM OF THE ROOF SUPPORTS NEAR THE CORNER POSTS. WHEN ATTACHING THE ROOF STARTER DIM B AT THE ROOF PEAK SHOULD MATCH DIM A. THIS WILL MAKE THE ROOF SUPPORTS PARALLEL TO EACH OTHER. DUE TO WOOD MILLING VARIATIONS YOUR HOLES IN THE ROOF STARTER WILL EITHER BE CENTERED ON THE ROOF SUPPORTS OR THEY WILL BE OFFSET TOWARDS THE INSIDE OF THE ROOF SUPPORTS SLIGHTLY. SUBTRACT DIM A FROM 76-7/8" AND THEN DIVIDE THIS NUMBER BY 2. THIS WILL GIVE YOU THE OVERHANG FOR EACH SIDE. USE THE OVERHANG NUMBER ON EACH SIDE TO KEEP YOUR ROOF SUPPORTS PARALLEL.



STEP 12: ROOF REAR SECTION AND CHIMNEY

ROOF BOARD INSTALLATION TIPS:

*INSTALL TWO ROOF BOARDS AND THEN REMOVE THE ROOF BOARD AT THE BOTTOM YOU ATTACHED TEMPORARILY.

*BEFORE FITTING ROOF BOARDS INTO ONE ANOTHER SIGHT DOWN THE BOARD TO SEE IF IT HAS A BOW TO IT. IF THE BOARD IS BOWED THEN PLACE THE "BOW SIDE UP". IT IS EASIER TO PUSH A BOW DOWN THAN TO PULL A BOW UP.

*SOMETIMES IT IS EASIER TO FIT BOARDS TOGETHER IF THE BOTTOM TWO SCREWS ARE LEFT OUT. INSTALL THE TWO SCREWS NEAR THE TOP OF THE ROOF BOARD AND LEAVE THE BOTTOM TWO HOLES EMPTY. THEN INSTALL THE NEXT ROOF BOARD BELOW IT AND ONLY INSTALL THE TWO TOP SCREWS IN THAT BOARD. GO BACK TO THE PRIOR BOARD AND INSTALL THE TWO BOTTOM SCREWS.

*USE A SCRAP BLOCK OF WOOD WITH A HAMMER TO HAMMER AGAINST ANY ROOF BOARDS THAT ARE DIFFICULT TO FIT. THIS SHOULD PREVENT DAMAGE TO THE ROOF BOARD.


1: PLACE THE 1 X 5 X 76-7/8" ROOF BOARDS ON TOP OF THE ROOF SUPPORTS, FITTING THE TONGUE END INTO THE GROOVE END OF THE ROOF STARTER REAR. THIS SIDE OF THE ROOF GETS SEVEN ROOF BOARDS.

2: FASTEN THE ROOF BOARDS TO THE ROOF SUPPORTS WITH 1-1/2" WOOD SCREWS.

3: PLACE THE 1 X 4 X 76-7/8" ROOF FINISHER AT THE END OF THE ROOF ASSEMBLY, AND FASTEN WITH 1-1/2" WOOD SCREWS.

4: MOUNT THE 2 X 4 X 69-3/4" ROOF FINISHER SUPPORT UNDERNEATH THE ROOF UP AGAINST THE ROOF FINISHER REAR AND ATTACH TO THE REAR CORNER POST USING 5/16" LAG SCREWS AND 5/16" WASHERS.

TIP: USE THE INSTRUCTIONS PROVIDED IN THE APPENDIX TO BUILD THE CHIMNEY. INSTALL THREE ROOF BOARDS AND INSTALL THE CHIMNEY ACCORDING TO THE CHIMNEY INSTRUCTIONS.




STEP 13: ROOF STARTER FRONT

IT MAY BE HELPFUL TO TEMPORARILY INSTALL A ROOF BOARD AT THE BOTTOM OF THE ROOF SUPPORTS. THAT WAY YOU CAN MAKE SURE THE FRONT CORNER POSTS STAY PARALLEL.

1: FASTEN THE ROOF BOARD AT THE END OF THE ROOF SUPPORTS WITH #8 X 1-1/2" WOOD SCREWS.

2: MEASURE THE DISTANCE ACROSS THE SET AT THE TOP OF THE POSTS. THAT DISTANCE SHOULD MATCH THE BOTTOM OF THE POSTS. IF THAT DISTANCE IS NOT THE SAME THEN LOOSEN THE SCREWS IN THE ROOF BOARD AND REPOSITION ON ONE SIDE UNTIL THE DISTANCES MATCH.




STEP 14: ROOF STARTER FRONT

1: PLACE THE 1 X 4 X 76-7/8" ROOF STARTER FRONT BOARD AT THE PEAK OF THE ROOF. THE HOLES IN THE ROOF STARTER SHOULD BE CENTERED ON THE ROOF SUPPORTS, AND THE FLAT TOP END OF THE FRONT (4") ROOF STARTER SHOULD OVERLAP THE OTHER REAR (3-1/4") ROOF STARTER.

2: FASTEN THE ROOF STARTER FRONT TO THE ROOF SUPPORTS WITH 1-1/2" WOOD SCREWS.


MEASURE DIM A ACROSS THE BOTTOM OF THE ROOF SUPPORTS NEAR THE CORNER POSTS. WHEN ATTACHING THE ROOF STARTER DIM B AT THE ROOF PEAK SHOULD MATCH DIM A. THIS WILL MAKE THE ROOF SUPPORTS PARALLEL TO EACH OTHER. DUE TO WOOD MILLING VARIATIONS YOUR HOLES IN THE ROOF STARTER WILL EITHER BE CENTERED ON THE ROOF SUPPORTS OR THEY WILL BE OFFSET TOWARDS THE INSIDE OF THE ROOF SUPPORTS SLIGHTLY. SUBTRACT DIM A FROM 76-7/8" AND THEN DIVIDE THIS NUMBER BY 2. THIS WILL GIVE YOU THE OVERHANG FOR EACH SIDE. USE THE OVERHANG NUMBER ON EACH SIDE TO KEEP YOUR ROOF SUPPORTS PARALLEL.




STEP 15: ROOF FRONT SECTION

1: PLACE THE 1 X 5 X 76-7/8" ROOF BOARDS ON TOP OF THE ROOF SUPPORTS, FITTING THE TONGUE END INTO THE GROOVE END OF THE ROOF STARTER FRONT. THIS SIDE GETS SEVEN ROOF BOARDS.

2: FASTEN THE ROOF BOARDS TO THE ROOF SUPPORTS WITH 1-1/2" WOOD SCREWS.






STEP 17: BOTTOM WALL BOARD 1: HAMMER A T-NUT INTO EACH HOLE IN THE FRONT CORNER POSTS. 2: FASTEN THE 2 X 4 X 70" BOTTOM WALL BOARD TO THE FRONT CORNER POSTS WITH 5/16" X 4-1/2" HEX BOLTS AND 5/16" WASHERS. 5/16" T-NUT WASHER⁻ T-NUT 5/16" X 4-1/2" HEX BOLT-2 X 4 X 70" BOTTOM WALL BOARD

STEP 18: ATTACHING THE FRONT GABLE

MOUNT THE GABLE ASSEMBLY RESTING ABOVE THE BOTTOM WALL BOARD. MAKE SURE THE GABLE ASSEMBLY IS FLUSH AGAINST THE FRONT CORNER POSTS. THE GABLE ROOF PEAK SHOULD BE RESTING ON TOP OF THE ROOF FRONT SECTION.

TIP: MAKE SURE THE DISTANCE BETWEEN THE GABLE ASSEMBLY AND THE ROOF OVERHANG IS EQUAL ON BOTH SIDES. IT IS RECOMMENDED TO TEST FIT THE 1 X 4 X 29.29" ROOF FINISHERS FRONT LEFT AND RIGHT TO ASSURE THIS EQUAL DISTANCE (DO NOT FASTEN). IF NECESSARY SLIDE THE GABLE ASSEMBLY LEFT OR RIGHT UNTIL FINAL POSITION IS ACCOMPLISHED.

2: THE GABLE ASSEMBLY BOTTOM COUNTERSUNK HOLES WILL REMAIN EMPTY FOR NOW.



STEP 19: WALL PANEL SUPPORTS

SINCE ALL INSTALLATIONS VARY THE 15-13/16" DIMENSION SHOWN MAY NOT BE CORRECT. FOLLOW THE PROCEDURE BELOW TO POSITION THE WALL PANEL BOARDS PROPERLY.


1: SLIDE THE LEFT ROOF FINISHER (NOT SHOWN) AGAINST THE ROOF BOARD TEMPORARILY. THEN PUSH THE WALL PANEL SUPPORT UNDER IT. THE TOP OF THE FINISHER NEEDS TO BE FLUSH TO THE TOP OF THE ROOF BOARD ABOVE IT.

2: SLIDE THE FINISHER OUT AND THEN MAKE A MARK AT THE END OF THE TIP OF THE WALL PANEL BOARD.

3: ALIGN THE BACK OF THE WALL PANEL SUPPORT FLUSH TO THE BACK OF THE GABLE ASSEMBLY. ALIGN THE TIP OF THE WALL PANEL BOARD WITH THE MARK. USE THE HOLE IN THE WALL PANEL BOARD TO DRILL A 1/8" PILOT HOLE THROUGH THE SHORT ROOF BOARD IN THE GABLE ASSEMBLY. INSTALL A 2-1/2" WOOD SCREW IN THE HOLE.

4: MAKE THE WALL PANEL SUPPORT PARALLEL TO THE ROOF BOARD. INSTALL A 5/16" X 3-1/2" LAG SCREW WITH 5/16" WASHER IN THE COUNTERBORED HOLE.

5: REPEAT SUBSTEPS 1 THROUGH 4 FOR THE RIGHT WALL PANEL SUPPORT.



47

STEP 20: ROOF FINISHERS FRONT


1: PLACE THE RIGHT ROOF FINISHER INTO THE GROOVE OF THE ROOF BOARD.

2: SLIDE THE FINISHER OVER UNTIL IT HITS THE GABLE ASSEMBLY ROOF. IF THE FINISHER STICKS OUT BEYOND THE END OF THE ROOF BOARD ABOVE IT THEN YOU WILL HAVE TO TRIM IT. MARK THE END OF THE FINISHER AND CUT IT TO LENGTH.

(IF THE FINISHER IS FLUSH TO THE END OF THE ROOF BOARD ABOVE IT THEN ALL YOU NEED TO DO IS TO ATTACH IT WITH THREE #8 X 1-1/2" WOOD SCREWS)

3: RESTAIN THE TRIMMED END OF THE FINISHER IF YOU CUT IT WITH THE STAIN PROVIDED.


4: AT THIS POINT YOU MAY NOTICE THAT THE TWO SMALL HOLES MAY NOT BE CENTERED OVER THE ROOF SUPPORT. IF THAT IS THE CASE THEN DRILL TWO SMALL HOLES THAT ARE CENTERED OVER THE ROOF SUPPORT AND INSTALL TWO #8 X 1-1/2" WOOD SCREWS.



STEP 21: ROOF BATTEN

1: PLACE THE 1 X 2 X 32" ROOF BATTEN UP AGAINST THE ROOF PANEL, CENTERED BETWEEN THE ROOF SUPPORTS. FLUSH THE BOTTOM EDGE OF THE ROOF BATTEN TO THE BOTTOM EDGE OF THE SEVENTH ROOF BOARD. MAKE SURE IT IS PARALLEL TO THE ROOF SUPPORTS. INSERT 1-1/4" SCREWS THROUGH THE PREDRILLED HOLES ALONG THE BATTEN AND SECURE THE BATTEN TO THE ROOF BOARDS. DO NOT OVERTIGHTEN THE SCREWS OR THE BATTEN COULD SPLIT.

2: REPEAT THIS PROCESS FOR THE SECOND ROOF BATTEN ON THE OTHER SIDE.



STEP 22: WALL PANEL BOARDS


1: START MOUNTING THE 1 X 4 X 19.31" WALL PANEL BOARD AGAINST THE GABLE LEFT ROOF SUPPORT AND THE WALL PANEL SUPPORT LEFT. THE SIDE EDGE OF THE WALL PANEL BOARD MUST BE PARALLEL AND 1/4" FROM THE SIDE EDGE OF THE FRONT LEFT CORNER POST. THE WALL PANEL BOARD BOTTOM ANGLED END SHOULD BE PARALLEL AND 1" FROM THE SIDE EDGE OF THE GABLE ROOF SUPPORT. FASTEN THE WALL PANEL BOARD WITH FOUR 1-1/2" WOOD SCREWS.

2: MOUNT THE 1 X 4 X 15.75" WALL PANEL BOARD AGAINST THE GABLE LEFT ROOF SUPPORT AND THE WALL PANEL SUPPORT LEFT. THE SIDE EDGE OF THE WALL PANEL BOARD MUST BE PARALLEL AND 1/4" FROM THE SIDE EDGE OF THE PREVIOUS WALL PANEL BOARD. THE WALL PANEL BOARD BOTTOM ANGLED END SHOULD BE PARALLEL AND 1" FROM THE SIDE EDGE OF THE GABLE ROOF SUPPORT. FASTEN THE WALL PANEL BOARD WITH FOUR 1-1/2" WOOD SCREWS.

3: MOUNT THE 1 X 4 X 12.25" WALL PANEL BOARD AGAINST THE GABLE LEFT ROOF SUPPORT AND THE WALL PANEL SUPPORT LEFT. THE SIDE EDGE OF THE WALL PANEL BOARD MUST BE PARALLEL AND 1/4" FROM THE SIDE EDGE OF THE PREVIOUS WALL PANEL BOARD. THE WALL PANEL BOARD BOTTOM ANGLED END SHOULD BE PARALLEL AND 1" FROM THE SIDE EDGE OF THE GABLE ROOF SUPPORT. FASTEN THE WALL PANEL BOARD WITH FOUR 1-1/2" WOOD SCREWS.

4: MOUNT THE 1 X 4 X 8.75" WALL PANEL BOARD AGAINST THE GABLE LEFT ROOF SUPPORT AND THE WALL PANEL SUPPORT LEFT. THE SIDE EDGE OF THE WALL PANEL BOARD MUST BE PARALLEL AND 1/4" FROM THE SIDE EDGE OF THE PREVIOUS WALL PANEL BOARD. THE WALL PANEL BOARD BOTTOM ANGLED END SHOULD BE PARALLEL AND 1" FROM THE SIDE EDGE OF THE GABLE ROOF SUPPORT. FASTEN THE WALL PANEL BOARD WITH FOUR 1-1/2" WOOD SCREWS.

5: REPEAT SUB-STEP 1 TO 4 FOR THE OTHER SIDE. ROOF BOARDS REMOVED FROM VIEW FOR CLARITY




STEP 23: GABLE BOARDS

1: PLACE THE 2 X 6 X 42" ROOF GABLE BOARD DIRECTLY UNDERNEATH THE ROOF SUPPORTS.

2: SECURE THE ROOF GABLE BOARD TO THE ROOF SUPPORTS WITH TWO #10 X 3-1/2" WOOD SCREWS.

3: REPEAT SUBSTEPS 1 THROUGH 2 FOR THE OTHER SIDE OF THE ROOF.



STEP 24: DORMERS

1: ASSEMBLE THE DORMERS AS SHOWN IN THE APPENDIX.


2: MAKE MARKS ON THE ROOF WITH A PENCIL AT THE DIMENSIONS SHOWN. NOTE THE DIMENSIONS START FROM THE JOINT OF THE SEVENTH ROOF BOARD AND THE FINISHERS.

3: INSTALL THE DORMER MOUNTING BLOCKS WITH TWO #8 X 2" WOOD SCREWS.

4: MOUNT THE DORMER 4-1/2" FROM THE BOTTOM EDGE OF THE SEVENTH ROOF BOARD. THE DORMER MOUNTING BLOCK WILL FIT BETWEEN THE SIDES OF THE DORMER.

5: ATTACH THE DORMER TO THE DORMER MOUNTING BLOCK WITH #8 X 2-1/2" WOOD SCREWS

6: INSTALL TWO 2" WOOD SCREWS FROM UNDERNEATH THE ROOF INTO THE DORMER MOUNTING BLOCKS.




STEP 25: WALL BOARDS LEFT SIDE

1: FIND SIX 1 X 6 X 51" WALL BOARDS AND TWO 1 X 4 X 51" WALL BOARDS WITH PRE-DRILLED HOLES.

2: PLACE WALL BOARDS ON THE LEFT SIDE OF THE FORT AGAINST THE ROOF GABLE BOARD AND THE SANDBOX BOARD AS SHOWN BELOW. THE BOTTOM OF THE WALL BOARDS SHOULD BE 1-3/8" ABOVE THE BOTTOM OF THE SANDBOX BOARD.


3: USE A #8 X 1-3/4" WOOD SCREWS TO ATTACH THE BOARDS. LEAVE 1/4" SPACES BETWEEN THE WALL BOARDS AS WELL AS THE CORNER POSTS.



53

STEP 26: ATTACHING PANEL BOARD BRACE


1: PLACE THE 1 X 3 X 40-1/2" PANEL BOARD BRACE AT THE CENTER OF THE WALL BOARDS YOU ATTACHED TO THE SWING BEAM SIDE. FASTEN IT TO THE WALL BOARDS WITH #8 X 1-1/4" WOOD SCREWS.




STEP 27: REAR WALL BOARDS

1: PLACE WALL BOARDS ON THE REAR SIDE OF THE FORT AGAINST THE BOTTOM PANEL BOARD AND THE ROOF FINISHER SUPPORT AS SHOWN BELOW. THE BOTTOM OF THE WALL PANEL BOARDS SHOULD BE FLUSH TO THE BOTTOM OF THE BOTTOM PANEL BOARD DOOR. THE OPENING DIMENSIONS FOR ATTACHING THE WINDOW IN THE NEXT STEP ARE SHOWN BELOW.

2: USE #8 X 1-3/4" WOOD SCREWS TO ATTACH THE WALL BOARDS. LEAVING 1/4" SPACES BETWEEN THE WALL BOARDS AS WELL AS THE CORNER POSTS.





STEP 29: WINDOW BOARD AND DOOR BOARD

1: PLACE THE 1 X 3 X 34-3/4" WINDOW BOTTOM BOARD FLUSH WITH THE BOTTOM OF THE WINDOW. THIS BOARD TIES THE BOARDS TOGETHER.


2: FASTEN THE WINDOW BOTTOM BOARD WITH #8 X 1-1/4" WOOD SCREWS.

3: PLACE THE 1 X 3 X 18" WINDOW TOP BOARD FLUSH WITH THE TOP OF THE WINDOW. THIS BOARD TIES THE BOARDS TOGETHER.


4: FASTEN THE WINDOW TOP BOARD WITH #8 X 1-1/4" WOOD SCREWS.

5: PLACE THE 1 X 6 X 27" ARCH TOP BOARD DOOR FLUSH WITH THE BOTTOM OF THE TOP DOOR BOARD 2 AND TOP DOOR BOARD 1 PIECES.

6: FASTEN THE ARCH TOP BOARD DOOR PIECE WITH #8 X 1-1/4" WOOD SCREWS.



STEP 30: RIGHT SIDE WALL BOARDS




STEP 31: PANEL BOARD BRACE AND TOP BOARD WINDOW

1: PLACE THE 1 X 3 X 40-1/2" PANEL BOARD BRACE FLUSH OR SLIGHTLY ABOVE THE BOTTOM BOARD OPEN WINDOW PIECES.

2: FASTEN WITH #8 X 1-1/4" WOOD SCREWS.

3: PLACE THE 1 X 6 X 34" TOP BOARD WINDOW FLUSH WITH THE OPEN WINDOW TOP BOARDS.


4: FASTEN WITH #8 X 1-1/4" WOOD SCREWS.



STEP 32: OPEN WINDOW OUTSIDE SUPPORT

1: PLACE THE 1 X 3 X 29-7/8" OPEN WINDOW OUTSIDE SUPPORT ON THE OUTSIDE OF THE RIGHT WALL BOARDS. MAKE THE TOP OF THE BOARD FLUSH TO THE TOP OF THE PANEL BOARD BRACE ON THE INSIDE.


2: FASTEN THE OPEN WINDOW OUTSIDE SUPPORT WITH #8 X 1-1/4" WOOD SCREWS.



STEP 33: OPEN WINDOW BOARD

1: PLACE THE 1 X 4 X 29-1/2" OPEN WINDOW BOARD ON TOP OF THE BOARDS IN THE WINDOW OPENING. THE BACK OF THE OPEN WINDOW BOARD SHOULD BE FLUSH TO THE INSIDE OF THE PANEL BOARD BRACE.

2: FASTEN THE OPEN WINDOW BOARD WITH #8 X 1-3/4" WOOD SCREWS.




STEP 34: PANEL SLATS

1: FIND SEVEN 5/4 X 6 X 28-1/4" PANEL SLATS.

2: INSTALL THE PANEL SLATS WITH EQUAL SPACING. SEE DETAILS BELOW FOR MEASUREMENTS.


3: ATTACH THE PANEL SLATS TO THE PLAYHOUSE WITH #8 X 2" WOOD SCREWS.



STEP 35: PANEL SLATS

1: PLACE THE 5/4 X 3 X 28-1/4" PANEL SLATS IN BETWEEN THE SLATS INSTALLED IN THE PREVIOUS STEP.


2: ATTACH THE PANEL SLATS TO THE PLAYHOUSE WITH #8 X 2" WOOD SCREWS.



STEP 36: DRILLING HOLES FOR FRONT ACCENT PIECES

1: USE THE DIMENSIONS ON THE LEFT TO MAKE CENTER MARKS FOR THE DIAGONAL ACCENT. THEN MEASURE 1" ABOVE AND BELOW EACH CENTER MARK TO MAKE THE SCREW HOLE MARKS. DRILL 1/8" HOLES AT THE SCREW HOLE MARKS. REPEAT THIS PROCESS AGAIN FOR THE BOARD ON THE OPPOSITE SIDE.

2: USE THE DIMENSIONS ON THE RIGHT TO MAKE CENTER MARKS FOR THE SCREW HOLES FOR THE VERTICAL ACCENT BOARD AT THE CENTER. DRILL 1/8" HOLES AT EACH MARK.




STEP 37: FRONT ACCENTS

1: PLACE THE 5/4 X 4 X 20-3/4" VERTICAL ACCENT CENTERED ON THE FRONT OF THE PLAYHOUSE. LET THE BOTTOM EDGE REST ON THE 2 X 5 X 70. FASTEN THE VERTICAL ACCENT FROM INSIDE GOING THROUGH THE SLAT INTO THE BACK SIDE OF THE VERTICAL ACCENT. USE #8 X 1-3/4" WOOD SCREWS TO SECURE THE VERTICAL ACCENT.

2: PLACE THE LEFT 5/4 X 4 X 28-3/8" DIAGONAL ACCENT FLUSH TO THE LEFT SIDE OF THE VERTICAL ACCENT AND LET THE TIP REST ON TOP OF THE 2 X 5 X 70. IF THE BOARD DOES NOT LOOK RIGHT THEN FLIP IT END FOR END AND PUT IT BACK INTO POSITION. FASTEN THE DIAGONAL ACCENT FROM THE INSIDE GOING THROUGH THE SLATS INTO THE BACK SIDE OF THE DIAGONAL ACCENT. USE #8 X 1-3/4" WOOD SCREWS TO SECURE THE DIAGONAL ACCENT.

3: PLACE THE RIGHT 5/4 X 4 X 28-3/8" DIAGONAL ACCENT FLUSH TO THE RIGHT SIDE OF THE VERTICAL ACCENT AND LET THE TIP REST ON TOP OF THE 2 X 5 X 70. IF THE BOARD DOES NOT LOOK RIGHT THEN FLIP IT END FOR END AND PUT IT BACK INTO POSITION. FASTEN THE DIAGONAL ACCENT FROM THE INSIDE GOING THROUGH THE SLATS INTO THE BACK SIDE OF THE DIAGONAL ACCENT. USE #8 X 1-3/4" WOOD SCREWS TO SECURE THE DIAGONAL ACCENT.




STEP 38: SOLAR WALL LIGHTS


1: WITH A PENCIL MAKE A CENTER MARK ON THE OUTSIDE FACE OF THE 1 X 4 X 19.31 WALL PANEL BOARD. MEASURE 4-7/8" HORIZONTALLY FROM THE OUTSIDE EDGE OF THE CORNER POST TOWARDS THE CENTER OF THE WALL PANEL BOARD AND 2-3/8" FROM THE BOTTOM EDGE OF THE WALL PANEL SUPPORT TOWARDS THE CENTER OF THE WALL PANEL BOARD AS SHOWN IN THE DIAGRAM BELOW.

2: PARTIALLY INSERT A #8 X 1" WOOD SCREW INTO THE WALL PANEL BOARD CENTER MARK FROM THE PREVIOUS SUB-STEP. MAKE SURE THE HEAD OF THE SCREW IS STICKING OUT ABOUT 3/8" FROM THE OUTSIDE FACE OF THE WALL PANEL BOARD.

3: MOUNT THE SOLAR WALL LIGHT ONTO THE WALL USING THE HEAD OF THE WOOD SCREW AS A HANGER INTO THE SLOT LOCATED IN THE BACK OF THE SOLAR WALL LIGHT. THE ON/OFF SWITCH IS LOCATED IN THE BOTTOM REAR OF THE SOLAR WALL LIGHT. YOU CAN ACCESS THIS SWITCH BY SWINGING THE SOLAR WALL LIGHT TOWARDS THE OUTSIDE OF THE CORNER POST.

4: REPEAT SUBSTEPS 1 TO 3 FOR THE OTHER SOLAR WALL LIGHT.





STEP 40: LEMONADE STAND SIGN

1: CUT TWO LENGTHS OF CHAIN TO 3-1/4" FROM THE PIECES PROVIDED.


2: HANG ONE END OF THE CHAIN ON THE END OF THE HOOK. PLACE THE OTHER END THROUGH THE HOLE ON THE LEMONADE STAND SIGN. PLACE THE END OF THE CHAIN ON THE HOOK. CLOSE THE HOOK WITH A PAIR OF PLIERS.

3: REPEAT SUBSTEP 2 FOR THE OTHER CHAIN.




PLIERS AFTER CHAIN IS INSTALLED. CUT CHAIN TO 3-1/4" LONG

DETAIL A SCALE 1 : 4



APPENDIX



| PICTURE | DESCRIPTION | QTY. |
|---------|--------------------------------------------------------|------|
| | DORMER SUNRAY ASSEMBLY 2-10-1355-DS | 4 |
| • • • | DORMER ROOF PANEL ASSEMBLY 2-13-1828-DRPA | 4 |
| | DORMER SIDE RIGHT ASSEMBLY 2-17-1850-DSRA | 2 |
| | DORMER SIDE LEFT ASSEMBLY 2-17-1850-DSLA | 2 |
| | DORMER MOUNT 2-3-1150-DM | 2 |
| | CHIMNEY FRONT ASSEMBLY 2-8-1500-CFA | 1 |
| | CHIMNEY RIGHT SIDE ASSEMBLY 2-10-1500-CRS | 1 |

| PICTURE | DESCRIPTION | QTY. |
|---------|-------------------------------------------------------|------|
| | Chimney left Side Assembly 2-10-1500-Cls | 1 |
| | CHIMNEY REAR ASSEMBLY 2-8-0700-CRA | 1 |
| | CHIMNEY MOUNTING BLOCK 2-3-0675-CMB | 1 |
| | | |
| | | |
| | | |
| | | |


STEP 1: DORMER SUNRAYS AND SIDES

1: FIND ONE DORMER SIDE LEFT ASSEMBLY AND ONE DORMER SIDE RIGHT ASSEMBLY.

2: FIND TWO DORMER SUNRAY ASSEMBLIES.

3: PLACE THE TWO DORMER SUNRAY ASSEMBLIES BETWEEN THE DORMER SIDE LEFT ASSEMBLY AND DORMER SIDE RIGHT ASSEMBLY. ONE DORMER SUNRAY ASSEMBLY FLUSH TO THE FRONT FLAT END OF THE DORMER SIDE ASSEMBLIES AND THE OTHER DORMER SUNRAY ASSEMBLY FLUSH TO THE REAR FLAT END OF THE DORMER SIDE ASSEMBLIES AS SHOWN BELOW.


4: ATTACH THE DORMER SIDE ASSEMBLIES TO THE DORMER SUNRAY ASSEMBLIES WITH #8 X 1-1/2" WOOD.



STEP 2: DORMER WINDOW

1: MOUNT THE DORMER WINDOW IN THE FRONT OF THE DORMER, THE WINDOW SHOULD FIT IN BETWEEN THE DORMER SIDES AND THE DORMER SUNRAY. THE BACK FACE OF THE WINDOW MUST BE RESTING AGAINST THE DORMER SIDES BATTENS.

2: MAKE SURE THE HOLES ON THE DORMER WINDOW ARE CENTERED WITH THE DORMER SIDES BATTENS AND THE DORMER SIDES ARE FLUSH TO THE SIDE EDGES OF THE DORMER WINDOW AND FASTEN WITH #8 X 1-1/2" WOOD SCREWS.





STEP 3: DORMER ROOF PANELS

1: FIND TWO DORMER ROOF PANEL ASSEMBLIES.

2: PLACE ONE DORMER ROOF PANEL ASSEMBLY ON TOP OF THE DORMER SUNRAY ASSEMBLIES, THE ROOF PANEL BOARDS MUST OVERHANG EQUALLY OFF THE FRONT AND BACK, MAKE SURE THE PRE-DRILLED HOLES ON THE ROOF PANEL ARE CENTERED WITH THE TOP FACE OF THE DORMER SUNRAY ASSEMBLES. FASTEN WITH #8 X 1-1/2" WOOD SCREWS.

3: REPEAT THE PREVIOUS SUB-STEP FOR THE OTHER SIDE.





STEP 5: CHIMNEY

1: ATTACH THE CHIMNEY SIDES FROM THE PREVIOUS SIDES TO FORM THE CHIMNEY WITH 2" AND 1-1/4" WOOD SCREWS.

__USE A 2" WOOD SCREW __IN THIS LOCATION (EACH SIDE)

USE 1-1/4" WOOD SCREWS IN THIS LOCATION (EACH SIDE)

